



# Leon County

## Board of County Commissioners

301 South Monroe Street, Tallahassee, Florida 32301  
(850) 606-5302 www.leoncountyfl.gov

Purchasing Division  
2284 Miccosukee Road  
Tallahassee, Florida 32308  
(850) 606-1600

Commissioners

BILL PROCTOR  
District 1

JANE G. SAULS  
District 2

JOHN DAILEY  
District 3

BRYAN DESLOGE  
District 4

BOB RACKLEFF  
District 5

CLIFF THAELL  
At-Large

AKIN AKINYEMI  
At-Large

PARWEZ ALAM  
County Administrator

HERBERT W.A. THIELE  
County Attorney

July 19, 2010

RE: Bid Title: Hawkbill Court Drainage Improvements  
Bid No: BC-08-05-10-46  
Opening Date: Thursday, August 5, 2010 at 2:00 PM

### ADDENDUM #1

Dear Vendor:

This letter serves as Addendum #1 for the above referenced project. The following shall be added to the bid specifications:

1. The proposed railing on the retaining wall shown on sheet 5 of the plans will be substituted with a Chain link fence. The fence will have a minimum height of four (4) feet and will vary in height to maintain an even elevation along the top of the retaining wall. The fence shall have a top rail. The contractor can refer to FDOT index 520 and 802 for additional information on the connection of the fence to the retaining wall. Contractor will submit fence details to Leon County for approval prior to construction.
2. Contractor shall note on sheet (4) the removal of the headwall of the driveway and shall make sure the pipe connects to the driveway culvert with a collar to ensure proper connection. The contractor shall maintain minimum cover of 12" over the pipe. After placement of the pipe the ground will be graded to channel the runoff to the ditch.
3. A new unit price sheet is attached and the one on-line updated.

Acknowledgment of this addendum is required as part of your bid submittal. Failure to acknowledge this addendum may result in rejection of your bid.

Should you have any questions, feel free to call me at (850) 606-1600.

Sincerely,

Don Tobin, CPPB  
Purchasing Agent

**HAWKBILL COURT BID SHEET (6/29/2010)**

ITEM NUMBER	ITEM DESCRIPTION	UNITS	QUANTITIES TOTAL	UNIT COST	SUB-TOTAL	NOTES
101-1	MOBILIZATION	LS	1		\$ -	Including application for staging area if required; construction stake out to be incidental.
102-1	MAINTENANCE OF TRAFFIC, INCLUDING ALL SIGNS	ED	60		\$ -	As shown in the construction plan.
102-74-2	TYPE III BARRICADE (MIN. 8)	ED	30		\$ -	See Sheet 3 for details.
104-10-1	BALED HAY OR STRAW (Ditch Blocks & Misc.)	EA	150		\$ -	Including stakes and necessary replacement.
104-11	TURBIDITY BARRIER (Floating)	LF	120		\$ -	
104-13-1	STAKED SILT FENCE, TYPE III	LF	150		\$ -	Replacement included.
110-1-1	CLEARING & GRUBBING (INCLUDING TREE REMOVAL)	AC	0.25		\$ -	Including backfill & disposal.
120-5	DITCH EXCAVATION CUT	CY	530		\$ -	Include disposal.
120-6	EMBANKMENT (DITCH FILL)	CY	145		\$ -	
120-72	GRAVEL FILL (#57 STONE, 2' BELOW STRUCTURE & EXTEND 12" OUTSIDE OF BOX)	CY	23		\$ -	Include materials, equipments & labors to place and grade to required depth.
160-6	TYPE B SUBBASE STABILIZATION (LBR 40)	SY	71		\$ -	See Sheet 5 & FDOT Index #307.
285-703	BASE GROUP (6" LIME ROCK LBR 100)	SY	68		\$ -	See Sheet 5 & FDOT Index #307.
339-1	MISCELLANEOUS ASPHALT PAVEMENT (1.25" SP-12.5 & 1.25" SP-9.5)	TN	7.5		\$ -	See Sheet 5 & FDOT Index #307.
400-1-1	CLASS I CONCRETE (BOX CULVERT 6' W X3' H & 56.16 LF)	CY	36		\$ -	See Sheet 5 & FDOT Index #289 & #292.
400-1-11	CLASS I CONCRETE (RETAINING WALLS)	CY	33		\$ -	
400-1-2	CLASS I CONCRETE (ENDWALLS)	CY	10		\$ -	
430-175-101	PIPE CULVERT OPTIONAL MATERIAL (18" CMP)	LF	20		\$ -	
550-10-210	CHAIN LINK FENCE	LF	102		\$ -	This will include all materials needed to construct the fence in accordance with the plans and Addendum 1.
524-1-2	CONCRETE DITCH PAVEMENT, NON-REINFORCED	SY	167		\$ -	Include incidental costs such as but not limited to No. 57 stone, geotextiles, wire mesh, control joints & expansion joints.
530-3	RUBBLE RIPRAP	TN	50		\$ -	Include no shrink grout and geotextiles.
536-1-1	GUARDRAIL - ROADWAY	LF	106		\$ -	Include materials, equipments & labors to construct guardrail per design plans.
536-85-22	GUARDRAIL - END ANCHORAGE ASSEMBLY - FLARED END	EA	4		\$ -	Include materials, equipments & labors to construct guardrail per design plans.
570-1-2	PERFORMANCE TURF (CENTIPEDE SOD)	SY	607		\$ -	Include bedding preparation, fertilization, lime application, & pins.
LC-001	LAW OFFICERS FOR MAINTENANCE OF TRAFFIC	ED	5		\$ -	For road closures.
LC-002	ARBORIST (TREE ASSESSMENT & MITIGATIONS)	LS	1		\$ -	Assess tree impacts and implement necessary mitigation plan.
LC-003	TURBIDITY CONTROL PLAN / WATER TREATMENT PLAN	LS	1		\$ -	When it is necessary, measures are needed to control turbidity level for construction site discharge water to comply with the State's Requirements for Lake Jackson OFW standards.
LC-004	DEWATERING/WATER BYPASSING	LS	1		\$ -	Best management practices should be followed.
LC-005	TREE PROTECTION BARRICADE	LF	255		\$ -	Replacement included.
LC-006	AS-BUILT SURVEY	LS	1		\$ -	
					\$ -	
					\$ -	
<b>TOTAL</b>					\$ -	