



GAS UTILITIES GENERAL NOTES AND SPECIAL PROVISIONS

PROJECT NAME	PROJECT NO.	FILE NO.	UTILITY AGENCY
Sharer Rd. Outfall Project			Gas Operations
Special Notations ()::			
<ol style="list-style-type: none"> 1. All construction activities related to installing new gas main or relocating the existing one will be done during project construction and will require cooperation of and timely coordination with the prime contractor. 2. All gas main placed out of service will be abandoned in place. It will be the roadway contractors responsibility to remove and dispose of said pipe if necessary. 3. The road contractor shall be responsible for any damage to gas facilities by said contractor or designees once gas installation/relocation is complete. 4. The road contractor shall notify The City Gas Dept. immediately if any gas main is nicked, scratched, cut or otherwise damaged so that repairs can be made promptly. 5. The City Gas Dept. requires 72 hours notice prior to any request for gas main exposure, protection or adjustment. 6. Approximately 2 calendar days will be required during project construction for completion of gas main installation/relocation. 7. It is the contractors responsibility to have all gas mains located prior to digging in vicinity of gas mains and to use due caution when doing so. 8. After installation of new gas main or relocation of existing gas mains as per 100% design plans, the City Gas Dept. will not be responsible for any conflicts due to design changes, field condition changes, addendums to contract or conflicts created by other utilities. 			