



ROSENBAUM ENGINEERING, INC.

1705 South Gadsden Street, Suite 100 • Tallahassee, FL 32301
Phone: 850-671-7230 • Fax: 850-671-7279

LEROY COLLINS LIBRARY ENTRANCE MODIFICATIONS

PROJECT NO. P11037.01.01

Date: November 7, 2012

ADDENDUM No. 1

REVISIONS TO THE DRAWINGS

1. SHEET C1.0
 - a. Addition of tree barrier fence and tree barricades per City Environmental comments.
 - b. Addition of wooden stringer to Tree Barrier Detail.
2. SHEET C1.2
 - a. Stop Bars shall be located 4 feet to the south of the pedestrian crossing striping.
 - b. The two Stop signs shown in triangular island are changed to Yield Signs.
 - c. The two Stop signs shall be located to the right of the new stop bar locations.
 - d. Add a yield sign to the north of the ADA ramp by the Right Only exit turn lane.
3. SHEET C3.2
 - a. Addition of Automation Equipment Vendor Notes.
4. SHEET U1.1
 - a. Addition of tree barrier fence and tree barricades per City Environmental comments.
 - b. Notes regarding hand trenching around Live Oak trees on western property boundary.
 - c. Note new location and depth of 2-1" conduit from Hub to Duval Street entrance.