



Leon County

Board of County Commissioners

301 South Monroe Street, Tallahassee, Florida 32301
(850) 606-5302 www.leoncountyfl.gov

Purchasing Division
1800-3 Blair Stone Road
(corner of Miccosukee and Blair Stone Roads)
Tallahassee, Florida 32308
(850) 606-1600

April 15, 2011

Commissioners

BILL PROCTOR
District 1

JANE G. SAULS
District 2

JOHN DAILEY
District 3

BRYAN DESLOGE
District 4

KRISTIN DOZIER
District 5

NICK MADDOX
At-Large

AKIN AKINYEMI
At-Large

PARWEZ ALAM
County Administrator

HERBERT W.A. THIELE
County Attorney

RE: Bid Title: Housing Rehabilitation, Group 2011-2
Bid No: BC-04-26-11-36
Opening Date: April 26, 2011 at 3:00 PM

ADDENDUM #2

Dear Vendor:

This letter serves as Addendum #2 for the above referenced project.

The following shall be added to the bid specifications:

Eddie and Barbara Johnson
4908 Lester Rd. 32317

- Add- 1. Build HVAC closet with 2068 "colonist" style hollow core door unit.
- 2. Replace existing package unit type heat pump with split system complete with new ductwork, electrical circuits, and required disconnects properly sized to heat and cool entire house. Remove and properly dispose of existing unit and ductwork. Abandon existing floor grills in place and permanently seal.
- 3. Increase cornice repairs to 50 l.f.
- 4. Install 5 smoke detectors per code.

Delete: Repair existing ductwork, construct chase in finished garage area.

James and Irene Hart
13695 Ulm Rd. 32309

- Add- 1. Remove and replace 13 windows. Materials and methods to be code compliant.
- 2. Construct HVAC closet complete with 2068 hollow core interior door unit to match existing doors as closely as possible.

Clara Boyd
5051 Bradfordville Road 32309

- Add- 1. Change number of porch posts from 4 to 5
- 2. Cultured marble vanity tops with integrated bowls may be used in lieu of plastic laminated tops and steel lavatory bowls.


Joyce Butler
4651 Gearhart Rd. 32303

- Add- 1. Increase kitchen wall cabinets from 6 l.f. to 10 l.f. allowing for vent hood cabinet.
2. Install correct piping from existing water heater pop-off valve through floor per code.
3. Remove existing strip decking and install 7/16" O.S.B. on entire roof area, approximately 1690 s.f.

Acknowledgment of this addendum is required as part of your bid submittal. Failure to acknowledge this addendum may result in rejection of your bid.

Should you have any questions, feel free to call me at (850) 606-1600.

Sincerely,



Don Tobin, CPPB
Purchasing Agent

DT