

INTERSECTION OF LAFAYETTE AND MAGNOLIA					
ROADWORK PAY ITEM					
Item No.	Item Description	Unit	Quantity	Unit Price	Total
0101 1	MOBILIZATION	LS	1		
0102 1	MAINTENANCE OF TRAFFIC	LS	1		
0104 10 3	SEDIMENT BARRIER	LF	182		
0104 18	INLET PROTECTION SYSTEM	EA	10		
0110 1 1	CLEARING & GRUBBING	AC	0.26		
0120 1	REGULAR EXCAVATION	CY	195		
0120 6	EMBANKMENT	CY	55		
0160 4	TYPE B STABILIZATION	SY	536		
0285701	OPTIONAL BASE,BASE GROUP 01	SY	101		
0285709	OPTIONAL BASE,BASE GROUP 09	SY	952		
0327 70 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	1,563		
0327 70 6	MILLING EXIST ASPH PAVT,1 1/2" AVG DEPTH	SY	2,146		
0334 1 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	743.0		
0425 2 61	MANHOLES, P-8, <10'	EA	1		
0425 1351	INLETS, CURB, TYPE P-5, <10'	EA	1		
0425 1361	INLETS, CURB, TYPE P-6, <10'	EA	1		
0425 1411	INLETS, CURB TYPE J-1, <10'	EA	1		
0425 1451	INLETS, CURB, TYPE J-5, <10'	EA	1		
0425 2 62	MANHOLES, P-8, >10'	EA	1		
0425 4	INLETS, ADJUST	EA	1		
<del>0425-5</del>	<del>MANHOLE, ADJUST</del>	<del>EA</del>	<del>5</del>		
<del>0425-6</del>	<del>VALVE BOXES, ADJUST</del>	<del>EA</del>	<del>13</del>		
0430175101	PIPE CULV, OPT MATL, ROUND, 0-24"S/CD	LF	184		
0520 1 8	CONCRETE CURB & GUTTER, SPECIAL	LF	855		
0520 1 10	CONCRETE CURB & GUTTER, TYPE F	LF	243		
0520 2 4	CONCRETE CURB, TYPE D	LF	145		
0522 1	SIDEWALK CONC, 4" THICK	SY	327		
0523 1 1	PATTERNED/TEXTURED PAVT/ASPH	SY	228		
0570 1 2	PERFORMANCE TURF, SOD	SY	357		
0700 20 11	SINGLE POST SIGN, F&I, LESS THAN 12 SF	AS	1		
0700 20 40	SINGLE POST SIGN, RELOCATE	AS	3		
0706 3	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	141		
0711 11111	THERMOPLASTIC, STD, WHITE, SOLID, 6"	NM	0.319		
0711 11123	THERMOPLASTIC, STD, WHITE, SOLID, 12"	LF	506		
0711 11125	THERMOPLASTIC, STD, WHITE, SOLID, 24"	LF	186		
0711 11160	THERMOPLASTIC, STD, WHITE, MESSAGE	EA	1		
0711 11170	THERMOPLASTIC, STD, WHITE, ARROW	EA	16		
0711 11211	THERMOPLASTIC, STD,YELLOW, SOLID, 6"	NM	0.377		
0711 11222	THERMOPLASTIC, STD, YELLOW, SOLID, 8"	LF	64		
0711 11224	THERMOPLASTIC, STD, YELLOW, SOLID, 18"	LF	56		
0711 17	THERMOPLASTIC, REMOVE	SF	150		
0999 99	TREE PROTECTION BARRICADE	LF	80		
LC-01	SURVEYING	LS	1		
	<b>Roadwork Total:</b>				
	<b>Signalization Total:</b>				
	<b>Utility Adjustment Total:</b>				
	<b>Project Total:</b>				
Items struck through above dealing with water and sewer adjustments - please refer to Attachment #4 and Pay Item sheet					
labeled water and sewer per City of Tallahassee					

<b>Magnolia/Lafayette Signalization</b>					
<b>PAY ITEM SHEET</b>					
<b>Item No.</b>	<b>Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Total</b>
555-1-1	Directional Bore (< 6")	LF	270.0		
630-1-11	Conduit (F&I) (Above Ground)	LF	20.0		
630-1-12	Conduit (F&I) (Underground)	LF	1065.0		
632-7-1	Cable (Signal) (F&I)	PI	1.0		
635-1-11	Pull & Junction Boxes (F&I) (Pull Box)	EA	19.0		
639-1-23	Electrical Power Service (Underground)	AS	1.0		
639-2-1	Electrical Service Wire (F & I)	LF	180.0		
641-2-12	Prestressed Concrete Poles (F&I) (Type P-II Pedestal) (12')	EA	1.0		
649-31-301	Mast Arm Assembly (F&I) (110) (Single Arm w/o Luminaire) (36')	EA	3.0		
649-31-303	Mast Arm Assembly (F&I) (110) (Single Arm w/o Luminaire) (60')	EA	1.0		
650-51-311	Traffic Signal (F&I) (3 Section, 1 Way)	AS	4.0		
650-51-511	Traffic Signal (F&I) (5 Section, 1 Way)	AS	4.0		
653-181	Pedestrian Signal (F&I) (LED International Symbol, Countdown) (1 Way)	AS	6.0		
653-182	Pedestrian Signal (F&I) (LED International Symbol, Countdown) (2 Way)	AS	1.0		
659-101	Signal Head Auxiliaries (F&I) (Back Plates, 3-Section)	EA	2.0		
659-107	Signal Head Auxiliaries (F&I) (Aluminum Pedestal)	EA	5.0		
659-118	Signal Head Auxiliaries (F&I) (Back Plates, 5-Section)	EA	2.0		
660-1-109	Loop Detector, Inductive (F&I) (Type 9, 2 Ch., SS, RM)	EA	4.0		
660-2-102	Loop Assembly (F&I) (Type B)	AS	8.0		
660-2-106	Loop Assembly (F&I) (Type F)	AS	4.0		
663-74-12	Vehicle Detector Assemblies (F&I) (Infrared)	EA	4.0		
665-11	Pedestrian Detector (F&I) (Pole Mounted)	EA	8.0		
670-5-121	Traffic Controller Assembly (F&I) (170) (One Preemption Plan)	AS	1.0		
690-10	Traffic Signal Head Assembly, Remove	EA	6.0		
690-32-1	Pole Removal - Shallow (Direct Burial)	EA	2.0		
690-50	Controller Assembly, Remove (Complete)	EA	1.0		
690-80	Span Wire Assembly, Remove	EA	1.0		
690-90	Cabling and Conduit, Remove	PI	1.0		
690-100	Signal Equipment, Miscellaneous Remove	PI	1.0		
699-1-1	Internally Illuminated Sign (F & I) (Street Name)	EA	4.0		
	<b>Signalization Total:</b>				<b>\$0.00</b>
<b>PAY ITEM NOTES:</b>					
<b>665-11:</b>	<b>INCLUDES FURNISHING AND INSTALLATION OF AUDIBLE / TACTILE PEDESTRIAN DETECTOR SYSTEM. F.D.O.T. APPROVED PRODUCT LIST (APL) CERTIFICATION #66513952018041. SYSTEM TO INCLUDE ONE (1) POLARA CCU WITH USB ETHERNET PORT (CCU2EN), ONE (1) POLARA PEDESTRIAN STATION MONITOR II (PSM2), EIGHT (8) POLARA EZ COMMUNICATION APS PEDESTRIAN STATION 9 BY 12 (EN29CN1-B), AND FOUR (4) 4.5" PEDESTRIAN POLE SPACERS (TWO BUTTON, 90 DEGREE MOUNTING) NPA4 BY 2-B.</b>				

