

ITEM	SUMMARY OF ROADWAY ITEMS	UNIT	QUANTITY
NUMBER	ITEM		
101 1	MOBILIZATION	LS	1
0102 1	MAINTENANCE OF TRAFFIC	LS	1
0102 60	WORK ZONE SIGN	ED	3,036
0102 74 2	BARRICADE, TEMPORARY, TYPE III, 6'	ED	792
0102 77	HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED	1,452
0102 99	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	264
0104 10 3	SEDIMENT BARRIER	LF	721
0104 11	FLOATING TURBIDITY BARRIER	LF	120
0110 1 1	CLEARING & GRUBBING	LS	1
0120 1	REGULAR EXCAVATION	CY	120
0120 6	EMBANKMENT	CY	78
0337 7 40	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FG-9.5, PG 76-22	TN	281.6
0400 1 2	CONCRETE CLASS I, ENDWALLS	CY	15.3
0415 1 1	REINF STEEL- ROADWAY	LB	1,072
0425 1521	INLETS, DT BOT, TYPE C, <10'	EA	6
0425 1544	INLETS, DITCH BOTTOM, TYPE D, J BOT, >10'	EA	1
0425 1541	INLETS, DT BOT, TYPE D, <10'	EA	2
0425 2 41	MANHOLES, P-7, <10'	EA	1
0425 2 71	MANHOLES, J-7, <10'	EA	1
0425 2 91	MANHOLES, J-8, <10'	EA	5
0425 2 92	MANHOLES, J-8, >10'	EA	5
0430 94 1	DESILTING PIPE, 0 - 24"	LF	109
0430174115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/SD	LF	48
0430175118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	176
0430175124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	160
0430175130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"S/CD	LF	184
0430175136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	1,736
0430602125	U-ENDWALL, WITH GRATE, STD 260, 1:4 SLOPE, 18"	EA	2
0430602129	U-ENDWALL, WITH GRATE, STD 260, 1:4 SLOPE, 24"	EA	1
0522 2	SIDEWALK CONCRETE, 6" THICK	SY	316
0530 1	RIPRAP, SAND-CEMENT	CY	33.9
0555 1 6	DIRECTIONAL BORE, 36" TO < 48"	LF	30
0570 1 2	PERFORMANCE TURF, SOD	SY	9,811
0700 20 40	SINGLE POST SIGN, RELOCATE	AS	10
0705 10 2	OBJECT MARKER, TYPE 2	EA	20
0710 11125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	LF	60

ITEM NUMBER	SUMMARY OF CULVERT REPLACEMENTS ITEMS	UNIT	QUANTITY TOTAL
0101 1	MOBILIZATION	LS	1
0102 1	MAINTENANCE OF TRAFFIC	LS	1
0102 60	WORK ZONE SIGN	ED	1440
0102 74 2	BARRICADE, TEMPORARY, TYPE III, 6'	ED	360
0102 77	HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED	1080
0102 99	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	240
0104 10 3	SEDIMENT BARRIER	LF	1855
0110 1 1	CLEARING & GRUBBING	LS	1
0120 1	REGULAR EXCAVATION	CY	120
0120 6	EMBANKMENT	CY	145
0400 1 2	CONCRETE CLASS I, ENDWALLS	CY	1.6
0430175115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	744
0430175118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	840
0430613323	U-ENDWALL, WITH BAFFLES & GRATE, STD 261, 1:2 SLOPE, 15"PIPE	EA	8
0430613325	U-ENDWALL, WITH BAFFLES & GRATE, STD 261,1:2 SLOPE,18"PIPE	EA	26
0430982123	MITERED END SECTION, OPTIONAL ROUND, 15" CD	EA	28
0430982125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	19
0522 2	SIDEWALK CONCRETE, 6" THICK	SY	1427
0570 1 2	PERFORMANCE TURF, SOD	SY	1170
0710 11125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	LF	14
Pay Item Notes:			
0110 1 1	All tree removal, including grinding stumps, shall be included in unit price for clearing and grubbing.		
0104-10-3	All tree protection barricades shall be paid for under sediment barrier pay item.		
0522-2	All removal of existing concrete driveways shall be included in unit price for sidewalk concrete, 6" thick.		
0430-175-115	Pay item includes cost replacement of concrete ditch pavement where needed.		
0430-175-118	Pay item includes cost of asphalt removal and replacement.		