

LAKESIDE DRIVE DRAINAGE IMPROVEMENTS

ITEM NUMBER	SUMMARY OF DRAINAGE IMPROVEMENTS ITEMS	UNIT	QUANTITY	UNIT COST	TOTAL COST
101 1	MOBILIZATION	LS	1		\$0.00
0102 1	MAINTENANCE OF TRAFFIC	LS	1		\$0.00
0104 10 3	SEDIMENT BARRIER	LF	441		\$0.00
0104 11	FLOATING TURBIDITY BARRIER	LF	120		\$0.00
0104 18	INLET PROTECTION SYSTEM	EA	10		\$0.00
0110 1 1	CLEARING & GRUBBING	LS	1		\$0.00
0110 15 2	ARBORIST WORK - COMPLETE	LS	1		\$0.00
0120 1	REGULAR EXCAVATION	CY	120		\$0.00
0120 6	EMBANKMENT	CY	78		\$0.00
0286 1	TURNOUT CONSTRUCTION	SY	76		\$0.00
0337 7 40	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FG	TN	226.1		\$0.00
0400 1 2	CONCRETE CLASS I, ENDWALLS	CY	12.9		\$0.00
0415 1 1	REINF STEEL- ROADWAY	LB	1,072		\$0.00
0425 1521	INLETS, DT BOT, TYPE C, <10'	EA	7		\$0.00
0425 1541	INLETS, DT BOT, TYPE D, <10'	EA	3		\$0.00
0425 2 41	MANHOLES, P-7, <10'	EA	1		\$0.00
0425 2 91	MANHOLES, J-8, <10'	EA	5		\$0.00
0425 2 92	MANHOLES, J-8, >10'	EA	7		\$0.00
0430 94 1	DESILTING PIPE, 0 - 24"	LF	109		\$0.00
430174115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	24		\$0.00
430175118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	270		\$0.00
430175124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	168		\$0.00
430175130	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 30"S/CD	LF	184		\$0.00
430175136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	1,760		\$0.00
430602125	U-ENDWALL, WITH GRATE,STD 260, 1:4 SLOPE, 18"	EA	4		\$0.00
430602129	U-ENDWALL, WITH GRATE,STD 260, 1:4 SLOPE, 24"	EA	1		\$0.00
0520 1 10	CONCRETE CURB & GUTTER, TYPE F	LF	120		\$0.00
0522 2	SIDEWALK CONCRETE, 6" THICK	SY	244		\$0.00
0530 1	RIPRAP, SAND-CEMENT	CY	40.5		\$0.00
0555 1 7	DIRECTIONAL BORE, 48" TO <60"	LF	30		\$0.00
0570 1 2	PERFORMANCE TURF, SOD	SY	9,689		\$0.00
0700 20 40	SINGLE POST SIGN, RELOCATE	AS	10		\$0.00
0705 10 2	OBJECT MARKER, TYPE 2	EA	30		\$0.00
0710 11125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, S	LF	60		\$0.00
1820 HP	6" RESTRAINED JOINT PVC WATER PIPE WITH PAVING	LF	30		\$0.00
5080	RECONNECT EXISTING WATER SERVICE	EA	14		\$0.00

**TOTAL
DRAINAGE
IMPROVEMENTS** \$0.00