

**ATTACHMENT A
SPECIFICATIONS
Miccosukee Road (CR347) Safety Project**

1. SUMMARY OF WORK

The proposed Miccosukee Road (CR 347) Safety Project is located in Section 8, 17, 18, 19, 24, 25, 26 & 35 Township 2 North, Range 3 East, in Leon County, Florida. This is a safety project to add signing and pavement markings on curves to address lane departures on Miccosukee Road.

2. GENERAL REQUIREMENTS

The construction sequence and design notes are shown on the construction plans. The contract administration, construction procedure, materials, and equipment, shall be in accordance with the following specifications and contract documents:

- 2.1 Florida Department of Transportation (FDOT) Standard Specifications for Road and Bridge Construction, 2013 Edition and all supplemental documents thereto.
- 2.2 Florida Department of Transportation (FDOT) Design Standards, 2012/2013
- 2.2 Manual on Uniform Traffic Control Devices (MUTCD), U.S. Department of Transportation Federal Highway Administration, Latest Edition.
- 2.4 U.S. Department of Transportation, Federal Highway Administration Manual on Standard Highway Signs, 2004, and the 2012 Supplement to the 2004 Standard Highway Signs.

3. MANDATORY PRE-BID CONFERENCE

Contractors are required to attend the pre-bid conference at the date and time specified in Section II., B., Schedule of Events of the ITB document. Contractors who do not have a representative present at the Mandatory Pre-bid Conference will be deemed non-responsive.

4. SPECIAL PROVISIONS

- 4.1 An allowance of 30 calendar days has been set for the completion of this Contract
- 4.2 A National Pollutant Discharge Elimination System (NPDES) General Permit for Storm Water Discharges from Construction Activities may apply to this Contract. It is the Contractor's responsibility to secure the NPDES permit prior to commencement of construction. A copy of the NPDES permit application form can be obtained through the Florida Department of Environmental Protection's (FDEP) web site at

http://www.dep.state.fl.us/water/stormwater/npdes/permits_forms.htm.

If a NPDES permit is obtained, a copy of the permit shall be provided to Leon County Public Works Department.

- 4.3 The liquidated damages will be set based on the bid price and according to Section 8-10 of the FDOT's Standard Specifications for Road and Bridge Construction, 2013 Edition.
- 4.4 It is the Contractor's responsibility to verify the survey control points for construction stakeouts as well as the wetland limits. The costs for construction stakeouts are considered incidental and included in the total bid price.

- 4.5 It is Contractor's responsibility to verify and locate all the utilities to avoid damages.
- 4.6 It is the Contractor's responsibility to establish a staging area with County representative's review and approval prior to commencement of construction. The Contractor is also responsible to obtain necessary permits if required by any other agencies. If the staging area is outside County's right-of-way or properties, the Contractor is required to obtain separate permits from Leon County Development Support and Environmental Services. All expenses associated with the additional permits will be paid by the Contractor.
- 4.8 The Contractor is also responsible to ensure all construction activities in compliance with the permit requirements.
- 4.9 Tree Protection and Root Pruning notes on plans must be adhered to.
- 4.10 The Contractor shall visit the project site prior to submitting the bids so a complete understanding of the site conditions and construction details can be achieved.
- 4.11 If the construction works causes any damages to adjacent properties, Contractor will be responsible for compensation unless it is proved otherwise.
- 4.12 The Contractor shall provide a minimum one-year warranty on the materials and workmanship for the work performed under this contract. The warranty shall commence upon completion of construction and issuance of Final Acceptance by the County.
- 4.13 The contractor will be required to develop and certify MOT and Detour plans prior to any closure will be approved.
- 4.14 As-built Survey and Record Drawings will be required for this project.
- 4.15 The Contractor or its subcontractor shall be certified by FDOT for maintenance of traffic.
- 4.16 The Contractor shall provide, as needed, a Sheriff's Deputy at their hourly rate, per Leon County's discretion. The Contractor shall pay the weekly invoice from the Sheriff's Department, and submit it to Leon County Public Works Department without any markup cost for reimbursement.