COMPONENTS OF CONTRACT PLANS SET

SIGNING AND PAVEMENT MARKING PLANS

SHEET NO.

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION

CONTRACT PLANS

FINANCIAL PROJECT ID 429673-2-58-01 LEON COUNTY (55540500) COUNTY ROAD NO. 347

INDEX OF SIGNING AND PAVEMENT MARKING PLANS

KEY SHEET 5-1 TABULATION OF QUANTITIES S-2 - S-3 GENERAL NOTES 5-4 GENERAL NOTES AND LEGEND 5-5 SIGNING AND PAVEMENT MARKING PLAN S-6 - S-22 SIGNING AND PAVEMENT MARKING PLAN S-23 - S-26 LOCATION ENLARGEMENT

SHEET DESCRIPTION

SIGNING AND PAVEMENT MARKING PLANS

MOCCASIN END PROJECT MP 6.39 MONTICELLO T-2-N

SIGNING AND PAVEMENT MARKING SHOP DRAWINGS TO BE SUBMITTED TO:

IACKSONVILLE

PIERCE

LAUDERDALE

PAUL VETTER, P.E. 3606 MACLAY BLVD. SOUTH, SUITE 201 TALLAHASSEE, FL 32312 TELEPHONE NO. 850-878-1971 FAX NO. 850-878-5345

PLANS PREPARED BY:

PAUL VETTER, P.E. 3606 MACLAY BLVD. SOUTH, SUITE 201 TALLAHASSEE, FL 32312 TELEPHONE NO. 850-878-1971 FAX NO. 850-878-5345 CERTIFICATE OF AUTHORIZATION NO. 2822 CONTRACT NO. C-926/ VENDOR NO. 95-408/636

NOTE: THE SCALE OF THESE PLANS MAY HAVE CHANGED DUE TO REPRODUCTION.

GOVERNING STANDARDS AND SPECIFICATIONS: FLORIDA DEPARTMENT OF TRANSPORTATION, DESIGN STANDARDS DATED 2012/2013 AND STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION DATED 2010. AS AMENDED BY CONTRACT DOCUMENTS.

APPLICABLE DESIGN STANDARDS REVISIONS: For Design Standards Revisions click on "Design Standards" at the following web site: http://www.dot.state.fl.us/rddeslgn/

BEGIN PROJECT

No. 59644

STATE OF

PROJECT LENGTH IS BASED ON & OF CONSTRUCTION

LENGTH (OF PROJEC	CT		KE	EY SHEET REVISIONS	SIGNING AND PAVEMEN
	LINEAR FEET	MILES	DA	TE	DESCRIPTION	MARKING PLANS ENGINEER OF RECORDS
ROADWAY	33,739.20	6.39				
BRIDGES						P.E. NO.
NET LENGTH OF PROJECT	33,739.20	6.39				
EXCEPTIONS						
GROSS LENGTH OF PROJECT	33,739.20	6.39				
FDOT PROJECT MANAGER: CRA	AIG GAVIN	SIGNING, PAVE (McCRACKEN F	MENT MAR ROAD) TO C	RKING . R 151 (i	AND FLASHER OF CR 347 F MOCCASIN GAP ROAD)	FROM SOUTH OF CR 348

Page 1

PENSACOLA

LOCATION OF PROJECT

SIGNING AND PAVEMENT ENGINEER OF RECORD: PAUL VETTER, P.E.

P.E. NO. 59644

FISCAL SHEET YEAR NO. 5-1

REVISIONS:

c:\pwworking\nat\Verseon\dms50863\KEYSSP0LDGN

Revised Attachment B - Miccosukee Road Signing and Pavement Marking Plans

TABULATION OF QUANTITIES

PAY	DESCRIPTION	IINIT									:	SHEET	NUMBERS	5									T01 TH		GRAND	F
ITEM NO.	DESCRIPTION	UNIT		-6		-7	S-			-9		-10		-11	S.	-12	5-1.	3	5-	14	S-I5		SHE		TOTAL	SF
02-1	MAINTENANCE OF TRUES O		PLAN	FINAL	PLAN	FINAL	PLAN	FINAL	PLAN	FINAL	PLAN	FINAL	PLAN	FINAL	PLAN	FINAL	PLAN I	FINAL F	PLAN	FINAL	PLAN F	INAL	PLAN	FINAL	PLAN F	INAL
2-1	MAINTENANCE OF TRAFFIC	L5	_		-																					
5-1-1	DIRECTIONAL BORE, LESS THAN 6"	LF																				-				
0-1-12 9-1-12	CONDUIT - SIGNALS, F&I, UNDERGROUND	LF																								
3-1-12	ELEC. PWR SERV. (OVRHD., PURCHASED BY CONTR.)	AS			-				_																	
9-2-1	ELECTRICAL SERVICE WIRE	LF										%				-	-					_				_
1-2-11	PD567050000 0010 0015 501 511 511 511 511 511																									
1-2-11	PRESTRESSED CONC. POLE, F&I, TYPE P-II SERV. POLE	EA																								
00-20-11	SINGLE POST SIGN, F&I. LESS THAN 12 SF	AS			9											-		_					9			
0-20-40	SINGLE POST SIGN, RELOCATE	AS	2																			-	2			
0-20-60	SINGLE POST SIGN, REMOVE	AS			2												1		- 1				4			
00-90-11	SIGN, FLASHING BEACON, F&I, GROUND MOUNT	AS	-		2							3 111											-			
																	1					-	3			
01-11-111	AUDIBLE & VIBRATORY PAVEMENT MARKING.	NM			0.239												0.242	0	. 537		0.466		1.484			
01-11-211	STANDARD, WHITE, SOLID, 6" AUDIBLE & VIBRATORY PAVEMENT MARKING,	NA			0.239												0.000									
	STANDARD, YELLOW, SOLID, 6"	TV do			0.233												0.242	- 0	.537		0.466		1.484			
																			1							
06-3	RETRO-REFLECTIVE PAVEMENT MARKER BIDIRECTIONAL YELLOW																									
	BIDIRECTIONAL TELLOW	EA			32												34		40		31		137			
1-11-125	THERMOPLASTIC, STANDARD, WHITE,	LF	12															_	-+		-	_	12			
	SOL ID. 24"																									
1-11-160	THERMOPLASTIC, STANDARD, WHITE,	EA		<u> </u>																						
17 100	MESSAGE, STOP	EA															1						- 1			
14-70-12	TRAFFIC MONITORING SITE, SOLAR POWER UNIT,	AS			2												1						3			
	EXISTING POLE																									
											-				-											_
				-																						
																	-					-				
										-																
																						-				
-31-19-																										
																			-							

		-					100	ARDESABRASAN	HANGING TO A	Tru-									-							
							CHILLIAN !	TF.	ETTE	Dalle.	-							-	-							
							1100	自然の を の の の の の の の の の の の の の	A C BEE	1 1/10																
							5 10	10-	196	100																
						Jan.		ceel	Vel	سيم	EN STATE OF THE ST							_		-						
						STATE OF THE PERSON NAMED IN COLUMN NAMED IN C	8	No.5	NSE 9644 97/9	10 S	7 20 20 20 20 20 20 20 20 20 20 20 20 20															
						(707) (722) (723) (724)	8		119	113: "	100															
						513 015 015 017	The state of the s	- mar 6. 1	re Of	# Q	THE STATE OF THE S									-						
						10	4 4	STA	LE OI	1 41	Tana and a second									-						
							E 10 %	FIL	Parai	4. 1	9															
							The CA	The same	NAL	1000																
							The state of the s	5511	MALY	CHACHER.																
							14	Wilder -	11111111111111111111111111111111111111	0																

		REVISIONS		PAUL VETTER. P.E.
DATE	DESCRIPTION	DATE	DESCRIPTION	P.E. LICENSE NUMBER 59644 JACOBS ENGINEERING GROUP, INC. 3606 MACLAY BLVD. SOUTH, SUITE 201 TALLAHASSEE, FL 32312 CFRTIFICATE OF AUTHORIZATION 282

DEPAI	STATE OF FR	LORIDA ANSPORTATION
ROAD NO.	COUNTY	FINANCIAL PROJECT ID
CR 347	LEON	429673-2-58-01

TABULATION OF QUANTITIES

SHEET NO. 5-2

Revised Attachment B - Miccosukee Road Signing and Pavement Marking Plans

TABULATION OF QUANTITIES

PAY		200.0000	SHEET NUMBERS						TO TH		GRAND		REI														
ITEM NO.	DESCRIPTION	UNIT		-16		-17	5-1			-19		-20		-21	S-	-22							SHE		TOTAL	Ĺ	SHE
02-1	MAINTENANCE OF TRAFFIC		PLAN	FINAL	PLAN	FINAL	PLAN I	FINAL	PLAN	FINAL	PLAN	FINAL	PLAN	FINAL	PLAN	FINAL	PLAN	FINAL	PLAN	FINAL	PLAN	FINAL	PLAN	FINAL	PLAN	FINAL	
		LS																				120					
55-1-1	DIRECTIONAL BORE, LESS THAN 6"	LF							275														275		275		
30-1-12	CONDUIT - SIGNALS, F&I, UNDERGROUND	LF							277														277		277		
39-1-12	ELEC. PWR SERV. (OVRHD., PURCHASED BY CONTR.)	AS							1														1		1		
39-2-1	ELECTRICAL SERVICE WIRE	LF							885			-											885		885		
1-2-11	PRESTRESSED CONC. POLE, F&I, TYPE P-II SERV. POLE	-5.																					883		883		
		EA																					- 1		1		
10-20-11 10-20-40	SINGLE POST SIGN, F&I, LESS THAN 12 SF SINGLE POST SIGN, RELOCATE	AS AS			2						1		1		1								5		14		
0-20-60	SINGLE POST SIGN, REMOVE	AS AS			,		1		— ,		1		1										5		2 9		
10-90-11	SIGN. FLASHING BEACON, F&I, GROUND MOUNT	46																					,				
		AS	'						-														3		6		
01-11-111	AUDIBLE & VIBRATORY PAVEMENT MARKING, STANDARD, WHITE, SOLID, 6"	NM	0.355				0.193		0.489														1.037		2.521		
01-11-211	AUDIBLE & VIBRATORY PAVEMENT MARKING.	NM	0.355				0.193		0.489			-											1.037		2.521		
	STANDARD, YELLOW, SOLID, 6"																						7105.		2.321		
06 - 3	RETRO-REFLECTIVE PAVEMENT MARKER																		-								
	BIDIRECTIONAL YELLOW	EA	24				13		58														95		232		
11-11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24"	LF																							12		
1-11-160	THERMOPLASTIC, STANDARD, WHITE,	EA																									
	MESSAGE. STOP	EA							-			-													- 1		
4-70-12	TRAFFIC MONITORING SITE, SOLAR POWER UNIT,	AS	1																								
	EXISTING POLE	AS	-				- 1				-	1		Vi									2		5		
																											\vdash
																											\vdash
											71																
							195	SALASSIASS	BEERLINES OF THE PARTY OF THE P	erosa.) (
							111111111111111111111111111111111111111	JUL	· VET	The aller																	\vdash
							Selle V	10 P. 10	ENS	24																	
								Page	ENS.	otto																	
								No.	59644	4 8	200																
									<i>★7/8</i>	3/13																	
							2 2 2	STA	TE O		in in																
								~ IP	1 - 1/1	82	Same.																
							1 O O	Way C	MLE.	1000																	
							1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Sin	TVI A	10,000																	
							100	Way I	Hart En water	20,200																	

		REVISIONS		PAUL VETTER. P.E.
DATE	DESCRIPTION	DATE	DESCRIPTION	P.E. LICENSE NUMBER 59644 JACOBS ENGINEERING GROUP, INC. 3606 MACLAY BLVD. SOUTH, SUITE 201 TALLAHASSEE, FL 32312 CERTIFICATE OF AUTHORIZATION 2823

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION									
ROAD NO.	COUNTY	FINANCIAL PROJECT ID							
CR 347	LEON	429673-2-58-01							

TABULATION OF QUANTITIES

SHEET NO.

7/8/2013

SIGNING AND PAVEMENT MARKING NOTES ----------

- SIGNING AND PAVEMENT MARKINGS ARE TO BE PLACED IN ACCORDANCE WITH THE 2009 MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, THE PLANS, THE SAFE MOBILITY FOR LIFE PROGRAM, THE FDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, AND THE FOOT DESIGN STANDARDS.
- 2. FOR SIGN DETAILS, USE THE MANUAL ON STANDARD HIGHWAY SIGNS PUBLISHED BY THE U.S. DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY ADMINISTRATION, 2004.
- THE CONTRACTOR SHALL CALL "SUNSHINE BII" AT 1-800-432-4770 OR BII A MINIMUM OF 2 BUSINESS DAYS BEFORE BEGINNING ANY EXCAVATION WORK.

COMPANY	TELEPHONE NUMBER	CONTACT PERSON
CENTURYLINK	850-599-1444	MANNY COSTILLA
TALQUIN ELECTRIC CO-OP, ELECTIC	850-627-7651	KEVIN WHYTE
CITY OF TALLAHASSEE TRAFFIC	850-891-5349	TOMMY SMITH
TALQUIN ELECTRIC CO-OP, WATER	850-627-7651	KEVIN GOSS
LEON COUNTY PUBLIC WORKS	850-666-1537	TONY PARK
CITY OF TALLAHASSEE UTILITIES	850-891-5031	TINA TROSE
CITY OF TALLAHASSEE UTILITIES	850-89 <i>1-503</i> 7	ALVIN WILLIAMS
(POWER SERVICE)		

- 4. ALL EXISTING SIGNS THAT CONFLICT WITH CONSTRUCTION OPERATIONS SHALL BE REMOVED, STOCKPILED AND RELOCATED BY THE CONTRACTOR. SIGN REMOVAL SHALL BE DIRECTED BY THE PROJECT ADMINISTRATOR. SIGNS THAT ARE TO BE REMOVED FROM THE PROJECT SHOULD BE STOCKPILED SEPARATELY FROM THOSE THAT ARE TO BE
- 5. CAUTION SHOULD BE EXERCISED WHILE RELOCATING EXISTING SIGNS TO PREVENT UNNECESSARY DAMAGE TO SIGNS. IF THE SIGNS ARE DAMAGED BEYOND USE, AS DETERMINED BY THE PROJECT ADMINISTRATOR, SIGNS SHALL BE REPLACED BY THE CONTRACTOR AT THEIR EXPENSE.
- CAUTION SHALL BE EXERCISED IN THE INSTALLATION OF POST MOUNTED SIGNS IN ORDER TO PREVENT POSSIBLE DAMAGE TO BURIED UTILITIES.
- ALL SIGNS WITHIN THE LIMITS OF THIS PROJECT SHALL REMAIN UNLESS OTHERWISE SHOWN IN THESE PLANS.
- B. THE PROJECT ADMINISTRATOR MAY REQUIRE THE CONTRACTOR TO FIELD ADJUST THE LOCATION OF ANY SIGN TO INSURE PROPER VISIBILITY.
- 9. THE CONTRACTOR IS TO MAINTAIN AND KEEP STREET NAME IDENTIFICATION VISIBLE DURING CONSTRUCTION OPERATIONS IN ORDER TO FACILITATE EMERGENCY VEHICLE TRAFFIC.
- 10. THE PAVEMENT MARKINGS AT ALL EXISTING/PROPOSED INTERFACE LOCATIONS ARE TO MATCH IN TERMS OF ALIGNMENT.
- II. THE REFLECTIVE PAVEMENT MARKERS ARE TO BE INSTALLED IN ACCORDANCE WITH STANDARD INDEX 17352 UNLESS OTHERWISE SHOWN IN THE PLANS.
- 12. ANY EXISTING THERMOPLASTIC OR PAINT MARKINGS THAT HAVE TO BE REMOVED FROM THE ROADWAY PAVEMENT MAY BE REMOVED BY ANY METHOD WHICH PRODUCES THE SAME RESULTS IN THE SAME MANNER AS HYDRO-BLASTING. THE USE OF BLACK PAINT TO COVER EXISTING AND/OR TEMPORARY PAVEMENT MARKINGS IS PROHIBITED.
- 13. NOT ALL EXISTING SIGNS ARE SHOWN. ONLY THOSE SIGNS PERTINENT TO THE PROJECT ARE SHOWN ON THE PLANS.
- 14. ITEM NOS. 701-11-111 AND 701-11-211 SHALL INCLUDE REMOVAL OF EXISTING PAVEMENT MARKING AND RAISED PAVEMENT MARKINGS (RPM). THEY SHALL BE PLACED ONLY AT THE LOCATIONS INDICATED.
- 15. SIGNS NOT LOCATED BY DIMENSIONING OR NOTE ON PLAN SHALL BE LOCATED BY SCALING.
- 16. THIS IS A TREE CANOPY ROAD AND ALL WORK IS SUBJECT TO THE REQUIREMENTS OF LEON COUNTY FOR TREE CANOPY ROADS. ALL IMPACT ON TREES SHALL RECEIVE PRIOR APPROVAL OF THE PROJECT ADMINISTRATOR.
- 17. THE CONTRACTOR SHALL PRESERVE ALL TREES WITHIN THE LIMITS OF CONSTRUCTION. A TREE PROTECTION BARRICADE IS TO BE INSTALLED AT OR NEAR THE CRITICAL PROTECTION ZONE OF EACH TREE DESIGNATED IN THE PLANS PRIOR TO INITIATION OF ANY CONSTRUCTION ACTIVITY AND IS TO REMAIN IN PLACE UNTIL ALL CONSTRUCTION ACTIVITY HAS BEEN COMPLETED. THE LEON COUNTY ENVIRONMENTAL INSPECTOR MUST APPROVE THE PLACEMENT OF THE TREE PROTECTION MEASURES.

and ()

- 18. ALL TREE ROOTS 3/4" IN DIAMETER AND LARGER EXPOSED DURING TRENCHING AND EXCAVATION SHALL BE CLEANLY CUT WITH A HANDSAW AND COVERED IMMEDIATELY WITH SOIL OR KEPT MOISTENED WITH WET BURLAP OR PEAT MOSS UNTIL THE TRENCH CAN BE FILLED. WHEN IT IS NOT POSSIBLE TO BACKFILL IN THE SAME DAY, THE ROOTS SHALL BE RE-CUT WITH A HANDSAW A REASONABLE DISTANCE FROM THE ORIGINAL CUT AND BACKFILLED IMMEDIATELY TO AVOID SOIL OR ROOT DEHYDRATION.
- 19. THE COUNTY WILL CONTRACT AN ARBORIST TO PREPARE A MITIGATION PLAN BEFORE CONSTRUCTION BEGINS. ARBORIST WILL MEET ONSITE WITH CONTRACTOR, ENGINEER AND ENVIRONMENTAL INSPECTOR PRIOR TO CONSTRUCTION TO ASSURE THAT THE WORK WILL BE OUTSIDE THE CANOPY PROTECTION ZONE OF I' FOR EVERY I" TREE DIAMETER.
- 20. ITEM 700-20-11: THE POSTS SHALL BE CHANNEL (W-TYPE) POSTS. THE MATERIAL AND INSTALLATION SHALL MEET THE LEON COUNTY STANDARDS/ REQUIREMENTS AND SHALL CONTAIN NO FOUNDATION.
- 21. THE USE OF HEAVY EQUIPMENT AND EQUIPMENT STAGING AREAS SHALL BE APPROVED BY LEON COUNTY PRIOR TO START OF CONSTRUCTION. THE LEON COUNTY ROOT PROTECTION STANDARDS SHALL BE FOLLOWED.

RETRO-REFLECTIVE PAVEMENT MARKER LEGEND: MD/Y: MONODIRECTIONAL YELLOW/CLEAR BD/Y: BI-DIRECTIONAL YELLOW/YELLOW BD W/R: BI-DIRECTIONAL WHITE/RED

FLASHING BEACON NOTES

- I. AS DIRECTED BY THE PROJECT ADMINISTRATOR, THE CONTRACTOR SHALL ADJUST CONDUIT IN ORDER TO AVOID ANY CONFLICTS WITH TREE ROOT SYSTEM AND UNDERGROUND UTILITIES.
- 2. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL UTILITIES PRIOR TO EXCAVATION.
- 3. THE CONTRACTOR WHO IS ENGAGED IN INSTALLING OR MAINTAINING TRAFFIC SIGNALS (INCLUDING FLASHING BEACONS) WITHIN DISTRICT THREE SHALL HAVE ALL WORK PERFORMED UNDER THE SUPERVISION OF A TECHNICIAN CERTIFIED BY THE INTERNATIONAL MUNICIPAL SIGNAL ORGANIZATION (IMSA) AS A LEVEL II, TRAFFIC SIGNALS TECHNICIAN. THE TECHNICIAN SHALL REPORT TO THE JOB SITE WITHIN FOUR HOURS OF NOTIFICATION TO THE WORK SITE SUPERVISOR TO CORRECT ANY PROBLEM OR EMERGENCY THAT MAY ARISE. IN ADDITION, A TECHNICIAN CERTIFIED AS AN I.M.S.A. LEVEL I TRAFFIC SIGNAL TECHNICIAN SHALL BE PRESENT ON THE JOB SITE AT ALL TIMES THE TRAFFIC SIGNALIZATION WORK IS IN PROGRESS.
- 4. THE CONTRACTOR SHALL PROVIDE A MINIMUM OF THREE SPARE CONDUCTORS AT EACH SIGNAL HEAD.
- 5. ALL SECTIONS OF VEHICULAR SIGNAL HEADS SHALL BE LED-TYPE.
- 6. SCHEDULE AN INSPECTION WITH MR. GENE SYFRETT [(850) 415-9669], OF THE DISTRICT THREE TRAFFIC OPERATIONS OFFICE BEFORE PLACING A NEW FLASHER INSTALLATION IN NORMAL OPERATION MODE.
- 7. THE CONTRACTOR TO FURNISH ALL TEST EQUIPMENT NECESSARY TO CONDUCT THE FIELD TESTS AT THE TIME OF THE INSPECTION, INCLUDING A BUCKET TRUCK. COMPENSATION FOR THIS EQUIPMENT AND ASSISTANCE SHALL BE INCLUDED IN THE ASSOCIATED PAY ITEM FOR ALL COMPONENTS OF THE SIGNALS TO UNDERGO TESTING.
- 8. USE CONDUITS OF SUFFICIENT SIZE TO ALLOW THE CONDUCTORS TO BE INSTALLED WITHOUT ANY DAMAGE AND MEETING NEC REQUIREMENTS. USE CONDUIT THAT IS AT LEAST TWO INCHES (50mm) IN DIAMETER, EXCEPT FOR ELECTRICAL POWER AND TELEPHONE SERVICE DUCTS, WHICH SHALL BE A MINIMUM OF ONE INCH (25mm) IN DIAMETER. VERIFY COLOR CODES FOR THE SIGNAL CABLE WITH THE LOCAL TRAFFIC SIGNAL MAINTAINING AGENCY PRIOR TO ORDERING MATERIAL.
- 9. VERIFY COLOR CODES FOR THE SIGNAL CABLE WITH THE LOCAL TRAFFIC SIGNAL MAINTAINING AGENCY PRIOR TO ORDERING MATERIAL.

7/8/2013

		REVISIONS	E S STATE	Om I I
DATE	DESCRIPTION	DATE	DESCRIP	TION FOR
			A SIONA	ENGINEER ST

PAUL VETTER, P.E. P.E. LICENSE NUMBER 59644 JACOBS ENGINEERING GROUP, INC. 3606 MACLAY BLVD. SOUTH, SUITE 201 TALLAHASSEE, FL 32312 CERTIFICATE OF AUTHORIZATION 2822

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION ROAD NO. COUNTY FINANCIAL PROJECT ID CR 347 LEON 429673-2-58-01

GENERAL NOTES

SHEET NO.

FLASHING BEACON NOTES CONTINUED

- II. INSTALL SIGNAL CABLE ONLY IN CONTINUOUS LENGTHS BETWEEN THE FLASHER AND THE CONTROLLER CABINET. SPLICE CABLE ONLY IN THE SIGNAL HEADS.
- 12. ITEM NO. 700-90-11 SHALL BE IN ACCORDANCE WITH INDEX NO. 17344, SHEET NO. 6 OF 6, AND SHALL CONTAIN A 4.5" DIA. ALUMINUM PIPE WITH 1/4" THICKNESS, COLOR GREEN TO MATCH THE SIGN CHANNEL POSTS AND A KEEPER PLATE AT THE PIPE BASE WHICH SHALL BE NO MORE THAN 3" ABOVE GRADE. THE FOUNDATION SHALL BE 2'-0" DIAMETER AND 4'-0" DEPTH IN GROUND WITH NO REINFORCING. THE SIGN SHALL BE MOUNTED WITH METAL BANDS AND BRACKETS. SOLAR PANELS ARE TO BE INCLUDED AT THE LOCATIONS INDICATED IN THE PLANS. REFER TO THE APPROVED PRODUCTS LIST (APL) FOR THE SOLAR PANELS.

 THE ASSEMBLY SHALL BE EQUIPPED WITH A MICROWAVE DOPPLER RADAR TO DETECT VEHICLE APPROACH SPEEDS THAT WILL ACTIVATE THE FLASHING BEACON. REFER TO THE APPROVED PRODUCTS LIST (APL) SPECIFICATION 660 FOR THE DIGITAL WAVE RADAR. THE BEACON SHALL BE OFF (BLANK) UNTIL ACTIVATED BY A PRE-CONFIGURED TRIGGER SPEED DETECTED BY THE RADAR AND FLASH FOR 4 TO 5 SECONDS DEPENDING ON THE APPROACH SPEED, AFTER WHICH THE BEACON WILL GO OFF UNTIL THE NEXT ACTIVATION. THE TRIGGER SPEEDS ARE SELECTED FROM A PRE-PROGRAMMABLE TABLE THAT IS SHOWN IN THE SPECIFICATIONS. THE SPEED DATA IS TO BE STORED IN THE UNIT AND CAN BE UTILIZED IN AN ANALYSIS TO CHANGE THE TRIGGER SPEED. SHALL INCLUDE A TREE PROTECTION BARRICADE AS SHOWN IN THE PLANS.
- 13. THE PAY ITEM FOR ELECTRICAL POWER SERVICE SHALL INCLUDE THE COST OF ANY PERMITS AND INITIAL CONNECTION FEES THAT MAY BE ASSESSED BY THE POWER COMPANY OR LOCAL GOVERNMENT, WHENEVER APPLICABLE. THIS APPLIES TO OVERHEAD AND UNDERGROUND SERVICES.
- 14. THE WORK TO BE ACCOMPLISHED BY THE POWER COMPANY INVOLVES DESCENT OF THEIR POLE WITH CONDUIT AND SERVICE CONDUCTORS TO A SECONDARY PEDESTAL SHOWN ON THE PLANS IN CLOSE PROXIMITY TO THE UTILITY POLE.
- 15. HAND-DIG THE FIRST 4 FEET OF POLE FOUNDATIONS.
- 16. INSTALL CONDUIT ACCORDING TO DESIGN STANDARDS, INDEX 17781, ALTERNATIVE NUMBER 2. UTILIZE THIS METHOD FOR ALL APPLICATIONS IN THE FDOT DISTRICT 3, WITHOUT REGARD TO THE PRESENCE OF CURB AND GUTTER.

REVISIONS

DATE

LEGEND

UP - UTILITY POLE

EOP - EDGE OF PAVEMENT

- EXISTING SIGN

- PROPOSED SIGN

DESCRIPTION

DATE



SPECIAL FLASHING BEACON NOTES

- I. FLASHING BEACONS SHALL BE LOCATED AS SHOWN IN THE PLANS.
- 2. LEON COUNTY IS THE MAINTAINING AGENCY.
- 3. LEON COUNTY SHALL ASSUME RESPONSIBILITY FOR THE POWER BILL.

MAINTENANCE OF TRAFFIC NOTES

- I. TRAFFIC SHALL BE MAINTAINED FOLLOWING THE FDOT DESIGN STANDARDS AND THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.
- 2. PAVEMENT MARKINGS SHALL BE PLACED BY CLOSING ONE LANE AT A TIME, FOLLOWING STANDARD INDEX NO.603. WORK SHALL BE PERFORMED BETWEEN THE HOURS OF 8:00 AM AND 5:00 PM.

DESCRIPTION	PAUL VETTER, P.E. P.E. LICENSE NUMBER 59644
	JACOBS ENGINEERING GROUP, INC. 3606 MACLAY BLVD. SOUTH, SUITE 201
	TALLAHASSEE, FL 32312 CERTIFICATE OF AUTHORIZATION 2822

DEF	STATE OF FLO PARTMENT OF TRAN	
ROAD NO.	COUNTY	FINANCIAL PROJECT ID
CR 347	LEON	429673-2-52-01

GENERAL NOTES
AND LEGEND

SHEET NO.

5-5









































