



Leon County

Board of County Commissioners

301 South Monroe Street, Tallahassee, Florida 32301
(850) 606-5302 www.leoncountyfl.gov

Purchasing Division
1800-3 Blair Stone Road
(corner of Miccosukee and
Blair Stone Roads)
Tallahassee, Florida 32308
(850) 606-1600

Commissioners

BILL PROCTOR

District 1

JANE G. SAULS

District 2

JOHN DAILEY

District 3

BRYAN DESLOGE

District 4

KRISTIN DOZIER

District 5

NICK MADDOX

At-Large

AKIN AKINYEMI

At-Large

VINCENT S. LONG

County Administrator

HERBERT W.A. THIELE

County Attorney

September 25, 2012

RE: Bid Title: Request for Proposals for Lafayette Street Sidewalk and Roadway Improvements
Bid No: BC-11-15-12-02
Opening Date: Thursday, November 15, 2012 at 1:00 p.m. Eastern Time

ADDENDUM #3

Dear Vendor:

This letter serves as Addendum #3 for the above referenced project.

The Draft RFP Attachment, "*Design-Build Criteria Package for Water and Wastewater Adjustments and Relocations*" is hereby amended as follows:

ADD the following text to Section 3.0 **SCOPE OF WORK**:

- z) Design and construct a replacement 8-inch gravity wastewater collection system from the intersection of Seminole Drive (i.e. approximately STA 440+00) to Magnolia Drive (i.e. approximately STA 454+00) including crossings, and from approximately STA 458+00 to STA 467+00, including crossings. The new gravity main will replace the existing 8-inch diameter clay sewer that is in poor condition. ONLY the existing gravity main on the north side of Lafayette Street needs to be replaced. The existing 8-inch clay gravity main on the south side of Lafayette Street may remain in-place, unless there are conflicts with new roadway and/or drainage features, in which case, such conflicts must be resolved by the Design-Build Firm.

All wastewater work shall be done in accordance with Section 7 of the *City of Tallahassee Standard Specifications for the Design and Construction of Water and Wastewater Facilities*, June 29, 2010, edition. The work also includes PVC wastewater piping, all reconnection of wastewater laterals, new wastewater cleanouts with castings, new manholes, drop connections, pavement restoration, and all incidental appurtenances necessary for a complete and functioning system. Install new terminal manholes where there are none presently (i.e. as of the release of the RFP).

Installation of gravity mains by other than open-cut methods is permissible. The means and methods of gravity wastewater main installation are left to the Design-Build Firm.

Acknowledgment of this addendum is required as part of your bid submittal. Failure to acknowledge this addendum may result in rejection of your bid. Should you have any questions, feel free to call me at (850) 606-1600.

Sincerely,

Handwritten signature of Shelly Kelley in blue ink.

Shelly Kelley, PMP
Purchasing Director

SWK