

NOTES:
 1. QUANTITIES SHOWN ON PLANS ARE FOR PRELIMINARY PURPOSES ONLY. CONTRACTOR IS RESPONSIBLE FOR HIS OWN QUANTITY TAKEOFFS AND SHALL PROVIDE MATERIAL SPECIFIED AT SPACING SCHEDULED TO FULLY FILL PLANT BEDS DRAWN ON PLANS.
 2. ALL LANDSCAPING SHALL BE PERFORMED TO MEET LEON COUNTY ENVIRONMENTAL MANAGEMENT ACT REQUIREMENTS AND STANDARDS OF GOOD NURSERY PRACTICE.
 3. ALL PLANT MATERIAL SHALL BE CONTAINER GROWN FROM INCEPTION AND PURCHASED FROM A QUALITY SOURCE.

ABBREVIATION:
 A.S. = AS SHOWN ON PLANTING PLANS.
 SPRD. = MIN. REQUIRED SPREAD, MEASURED AS AVERAGE DIAMETER OF FOLIAGE.
 HT. = MIN. REQUIRED HEIGHT, MEASURED FROM GROUND UP.
 O.C. = ON CENTER SPACING

PLANT SCHEDULE - ROADWAY

PAY ITEM #	TREES (EDGES @ RW): SYMBOL	QUANTITY	BOTANICAL NOMENCLATURE	COMMON NAME	SPACING / SIZE / REMARKS	MAINTENANCE GUIDELINES
2583-7-	MCT	77	MYRICA CERIFERA (TREE FORM)	WAX MYRTLE	9' O.C. 7' TO 8' HT., MULTI TRUNK (MAX. 3 TRUNKS)	TRIM TO MAINTAIN LIMITS OF CLEAR SIGHT SHOWN ON TYPICAL SECTION.
2583-7-	AP	183	ACER PALMATUM (BLOOD GOOD)	JAPANESE MAPLE	13' O.C. / 7' TO 8' HT.	TRIM TO MAINTAIN LIMITS OF CLEAR SIGHT SHOWN ON TYPICAL SECTION.
2583-7-	LIS	46	LAGERSTROEMIA INDICA 'SIOUX'	SIOUX CREPE MYRTLE	9' O.C. 8' TO 10' HT.	TRIM TO MAINTAIN LIMITS OF CLEAR SIGHT SHOWN ON TYPICAL SECTION.
2583-7-	LIN	7	LAGERSTROEMIA INDICA "NATCHEZ"	"NATCHEZ WHITE" CREPE MYRTLE	A.S. / 14' TO 16' HT., 1 1/4" TO 2" CAL., 5' TO 6' SPRD.	TRIM TO MAINTAIN LIMITS OF CLEAR SIGHT SHOWN ON TYPICAL SECTION.
2581-3-	CR	28	ROSASP	CHEROKEE CLIMBING ROSES	AT EVERY OTHER FENCE POST, 1 GAL.	DO NOT TRIM, ENCOURAGE FENCE COVERAGE/CLIMBING

PAY ITEM #	SYMBOL	QUANTITY	BOTANICAL NOMENCLATURE	COMMON NAME	SPACING / SIZE / REMARKS	MAINTENANCE GUIDELINES
2583-7-	AR	18	ACER RUBRUM	'SWAMP' RED MAPLE	A.S. 8'-10' HT., 4'-5' SPRD. 2"-2 1/2" CAL. 30 GAL. FULL BRANCHING & FOLIAGE	
2583-7-	SB	2	SALIX BABYLONICA	WEeping WILLOW	A.S. 10'-12' HT., 6'-8' SPRD. 2"-2 1/2" CAL. 30 GAL. FULL BRANCHING & FOLIAGE	
2583-7-	TD	13	TAXODIUM DISTICHUM	BALD CYPRESS	A.S. 7'-8' HT., 4'-5' SPRD. 2"-2 1/2" CAL. 30 GAL. FULL BRANCHING & FOLIAGE	

PAY ITEM #	SYMBOL	QUANTITY	BOTANICAL NOMENCLATURE	COMMON NAME	SPACING / SIZE / REMARKS	MAINTENANCE GUIDELINES
2582-2-	AI	48	AZALEA INDICA	AZALEA	4' O.C., 24" HT., 1 GAL FULL FOLIAGE TO GROUND	
2582-2-	IA	165	ILLICIUM ANISATUM	FLORIDA ANISE	5' O.C., 24" HT., 1 GAL. FULL FOLIAGE TO GROUND	
2582-2-	MC	162	MYRICA CERIFERA	WAX MYRTLE	5' O.C., 24"-30" HT. & SPRD., 3 GAL.	TRIM TO MAINTAIN FULL DENSITY TO THE GROUND

SHRUBS