

**PLANTING SCHEDULE - ROADWAY**

**PLANTING SCHEDULE - PONDS**

**ABBREVIATION:**  
 A.S. = AS SHOWN ON PLANTING PLANS.  
 SPRD. = MIN. REQUIRED SPREAD, MEASURED AS AVERAGE DIAMETER OF FOLIAGE.  
 HT. = MIN REQUIRED HEIGHT, MEASURED FROM GROUND UP.  
 O.C. = ON CENTER SPACING

**NOTES:**  
 1. QUANTITIES SHOWN ON PLANS ARE FOR PRELIMINARY PURPOSES ONLY. CONTRACTOR IS RESPONSIBLE FOR HIS OWN QUANTITY TAKEOFFS AND SHALL PROVIDE MATERIAL SPECIFIED AT SPACING SCHEDULED TO FULLY FILL PLANT BEDS DRAWN ON PLANS.  
 2. ALL LANDSCAPING SHALL BE PERFORMED TO MEET LEON COUNTY ENVIRONMENTAL MANAGEMENT ACT REQUIREMENTS AND STANDARDS OF GOOD NURSERY PRACTICE.  
 3. ALL PLANT MATERIAL SHALL BE CONTAINER GROWN FROM INCEPTION AND PURCHASED FROM A QUALITY SOURCE.

PAY ITEM #	TREES (EDGES @ RW): SYMBOL	QUANTITY	BOTANICAL NOMENCLATURE	COMMON NAME	SPACING / SIZE / REMARKS	MAINTENANCE GUIDELINES
2583-7-	AP	26	ACER PALMATUM (BLOOD GOOD)	JAPANESE MAPLE	13' O.C. / 7' TO 8' HT., 4' TO 6' SPRD.	TRIM TO MAINTAIN LIMITS OF CLEAR SIGHT SHOWN ON TYPICAL SECTION.
GROUND COVERS (MEDIAN):						
2581-3-	CR	14	ROSASPP	CHEROKEE CLIMBING ROSES	AT EVERY OTHER FENCE POST, 1 GAL.	DO NOT TRIM. ENCOURAGE FENCE COVERAGE/CLIMBING
2583-7-	TD	5	TAXODIUM DISTICHUM	BALD CYPRESS	A.S. 7'-8' HT., 4'-5' SPRD. 2"-2 1/2" CAL.	
2583-7-	SB	1	SALIX BABYLONICA	WEeping WILLOW	A.S. 10'-12' HT., 6'-8' SPRD. 2"-2 1/2" CAL.	
2582-2-	IA	132	ILLICUM ANISATUM	FLORIDA ANISE	5' O.C., 24" HT., 1 GAL. FULL FOLIAGE TO GROUND	