

PAY ITEM NOTES:

GENERAL:

1. NO SEPARATE PAYMENT WILL BE MADE FOR DEWATERING. THE COSTS FOR DEWATERING ARE INCLUDED IN THE UNIT PRICES FOR CONCRETE PIPE CULVERT AND OTHER ITEMS AS DESCRIBED IN THE PAY ITEM NOTES.
2. NO SEPARATE PAYMENT WILL BE MADE FOR FILTER FABRIC. THE COSTS FOR FILTER FABRIC ARE INCLUDED IN THE UNIT PRICES FOR CONCRETE PIPE CULVERT, CONCRETE BOX CULVERT, HEADWALLS AND OTHER ITEMS AS DESCRIBED IN THE PAY ITEM NOTES.
3. ADDITIONAL QUANTITIES OF EROSION CONTROL AND/OR TREE PROTECTION ITEMS MAY BE NECESSARY AS DETERMINED DURING CONSTRUCTION BY THE CONTRACTOR AND APPROVED BY THE ENGINEER.

PAY ITEMS:

101-1 MOBILIZATION:

THE UNIT PRICE ALSO INCLUDES ALL COSTS FOR PREPARATION OF AN APPROVED CONSTRUCTION PROGRESS SCHEDULE, AN APPROVED PRECONSTRUCTION SURVEY, AN APPROVED TRAFFIC CONTROL PLAN, AN APPROVED DEWATERING PLAN, AN APPROVED SEDIMENT AND EROSION CONTROL PLAN, AND FURNISHING, INSTALLING AND REMOVING THE PROJECT SIGNS.

102-1 MAINTENANCE OF TRAFFIC:

THE UNIT PRICE CONSTITUTES FULL COMPENSATION FOR ALL LABOR AND MATERIALS REQUIRED TO SAFELY MAINTAIN TRAFFIC AROUND OR THROUGH THE WORK ZONE NOT INCLUDED FOR PAYMENT UNDER OTHER RELATED PAY ITEMS, INCLUDING WARNING AND REGULATORY SIGNS, MESSAGE BOARDS, DRUMS, BARRICADES, CHANNELIZING DEVICES, TEMPORARY CONCRETE BARRIER, WARNING LIGHTS, FLAGGERS, AND FOR THE MAINTENANCE OF EXISTING DRIVEWAYS, TEMPORARY PAVEMENT, AND REMOVAL AND REINSTALLATION OF EXISTING SIGNS IN CONFLICT WITH CONSTRUCTION AS DIRECTED BY THE ENGINEER.

104-110 FLOATING TURBIDITY BARRIER:

THE UNIT PRICE CONSTITUTES FULL COMPENSATION FOR ALL LABOR AND MATERIAL NECESSARY FOR THE INSTALLATION OF TURBIDITY BARRIERS TO PROTECT AGAINST DOWNSTREAM ACCUMULATION OF SEDIMENT AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.

104-18 RUBBLE RIPRAP INCLUDING CEMENT AND FILTER FABRIC UNDERLAY:

THE UNIT PRICE CONSTITUTES FULL COMPENSATION FOR ALL LABOR AND MATERIALS NECESSARY FOR THE INSTALLATION AND MAINTENANCE OF RUBBLE RIPRAP.

110-1-1 CLEARING AND GRUBBING:

THE UNIT PRICE ALSO INCLUDES REMOVAL AND DISPOSAL OF CURBS, SIDEWALKS, DRIVEWAYS, DRAINAGE STRUCTURES, PIPES, SIGNING AND STRIPING AND ALL OTHER STRUCTURES AND OBSTRUCTIONS NECESSARY TO BE REMOVED AND FOR WHICH OTHER ITEMS OF THE CONTRACT DO NOT SPECIFY THE REMOVAL THEREOF. PARTIAL PAYMENTS WILL BE BASED UPON THE ESTIMATED TOTAL VALUE OF WORK COMPLETED TO THE DATE OF THE ESTIMATE AS DETERMINED BY THE ENGINEER. ALL PARTIAL ESTIMATES AND PAYMENTS ARE SUBJECT TO CORRECTION IN SUBSEQUENT ESTIMATES AND PAYMENT.

125-3 SELECT BEDDING MATERIAL:

THE UNIT PRICE CONSTITUTES FULL COMPENSATION FOR ALL WORK REQUIRED FOR FURNISHING, PLACING, AND COMPACTING SELECT MATERIAL FOR THE INSTALLATION OF CONCRETE PIPE TO THE LIMITS AND DENSITIES SPECIFIED ON THE PLANS. FINAL PAY QUANTITY WILL BE PLAN QUANTITY WITH NO CONSIDERATION FOR SPECIFICATION TOLERANCES.

430-175-118, 430-175-124, 430-175-130, 430-175-136, 430-175-5334 CONCRETE PIPE CULVERT (CLASS III):

THE UNIT PRICE ALSO INCLUDES PAYMENT FOR SHEETING AND/OR SHORING, DEWATERING, FILTER FABRIC, PLACING, AND COMPACTING SELECT BEDDING MATERIAL TO THE LIMITS AND DENSITIES SHOWN ON THE PLANS, AND FURNISHING SELECT MATERIAL FOR BACKFILL WHEN SUITABLE MATERIAL IS NOT AVAILABLE ON SITE.

334-1-2 SUPERPAVE ASPHALTIC CONCRETE

THE UNIT PRICE ALSO INCLUDES ADJUSTMENT OF ALL EXISTING UTILITY FRAMES AND COVERS AND ALL WATER AND GAS VALVES WITHIN THE LIMITS OF CONSTRUCTION TO BE FLUSH WITH FINISHED PAVEMENT AND ALL REQUIRED SIGNING AND STRIPING.

410-70-063, 410-70-085 PRECAST CONCRETE BOX CULVERT

THE UNIT PRICE CONSTITUTES FULL COMPENSATION FOR ALL LABOR AND MATERIALS NECESSARY TO FURNISH AND INSTALL PRECAST REINFORCED CONCRETE BOX CULVERT INCLUDING REINFORCING STEEL, SHEETING AND/OR SHORING, DEWATERING, FILTER FABRIC, FURNISHING SELECT MATERIAL FOR BACKFILL WHEN SUITABLE MATERIAL IS NOT AVAILABLE ON-SITE, AND FOR FURNISHING AND PLACING A 1-1/2" MINIMUM THICKNESS OF ASPHALT PAVEMENT MILLINGS OR FINE TYPE SP ASPHALTIC CONCRETE AT THE GROUND SURFACE OF PIPE TRENCHES IN PAVED AREAS FOR SEDIMENT AND EROSION CONTROL UNTIL THE FINAL PAVEMENT IS PLACED.

430-830 PIPE FILLING AND PLUGGING

THE UNIT PRICE CONSTITUTES FULL COMPENSATION FOR ALL LABOR AND MATERIALS REQUIRED TO PERMANENTLY PLACE EXISTING PIPE CULVERTS OUT OF SERVICE IN ACCORDANCE WITH SECTION 430-4.5 OF THE STANDARD SPECIFICATIONS.

530-76-2: GABION MAT

THE UNIT PRICE INCLUDES FULL COMPENSATION FOR ALL LABOR, MATERIALS, AND INCIDENTALS REQUIRED FOR THE CONSTRUCTION OF GABION MATS AS SHOWN ON THE PLANS.

550-10-919 FENCING, 4" BLACK VINYL COATED

THE UNIT PRICE CONSTITUTES FULL COMPENSATION FOR ALL LABOR AND MATERIALS REQUIRED FOR INSTALLATION OF 4" BLACK VINYL COATED FENCE AS SHOWN ON THE PLANS. ALL MATERIALS INCLUDING POSTS, POST CAPS, RAILS, TIES, TRUSS RODS, FASTENERS, TENSION BARS, MESH, ETC. SHALL BE BLACK.

570-1-2: PERFORMANCE TURF (SODDING)

THE UNIT PRICE CONSTITUTES FULL COMPENSATION FOR ALL LABOR, MATERIALS, AND INCIDENTALS REQUIRED FOR ESTABLISHING A STAND OF GRASS BY SODDING, INCLUDING FURNISHING AND PLACING SOD, FERTILIZER, WATER, AND MAINTENANCE.

580-340-1: TREE PROTECTION

THE UNIT PRICE CONSTITUTES FULL COMPENSATION FOR ALL LABOR, MATERIALS, AND INCIDENTALS NECESSARY FOR THE INSTALLATION AND MAINTENANCE OF TREE PROTECTION BATTER BOARDS, INCLUDING MATERIAL AND POSTS, AND REMOVAL AND DISPOSAL OFF SITE OF TREE PROTECTION BATTER BOARDS UPON COMPLETION OF CONSTRUCTION.

999-1-1: DEMOLITION REQUIRED ON LOTS 4 AND 5

THE UNIT PRICE CONSTITUTES FULL COMPENSATION FOR ALL LABOR AND MATERIALS NECESSARY FOR THE DEMOLITION AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER INCLUDING ASBESTOS TESTING AND OFF-SITE DISPOSAL OF WASTE MATERIALS. DEMOLITION SHALL INCLUDE PROPER ABANDONMENT OF SEPTIC TANKS PER LEON COUNTY HEALTH DEPARTMENT AND CITY OF TALLAHASSEE/LEON COUNTY ACQUIFER PROTECTION PROGRAM REGULATIONS.

999-1-2 ASBUILT SURVEY

THE UNIT PRICE CONSTITUTES FULL COMPENSATION FOR ALL LABOR AND MATERIALS FOR ASBUILT SURVEY OF ALL IMPROVEMENTS AND VIDEO DOCUMENTATION OF ALL NEW PIPE CONSTRUCTED.



930 THOMASVILLE ROAD
SUITE 200
TALLAHASSEE, FLORIDA 32303
PHONE 850.286.4213
FAX 850.286.4498
WWW.INOVIAGROUP.COM
CAB225

NO.	BY	REVISIONS	DATE

PROJECT NO.: 25.004.00
DRAWING FILE: J:\PROJECTS\25\10025.004.00\DWG\BASE.DWG

CLIENT	LEON COUNTY PUBLIC WORKS
PROJECT	BEN BOULEVARD INFRASTRUCTURE IMPROVEMENTS
SHEET	PAY ITEM NOTES

PLAN RELEASE STATUS	PROGRESS PRINT
PERMIT RELEASE	
BID RELEASE	
CONSTRUCTION RELEASE	
RELEASE DATE: 13 OCT 11	INITIAL DATE
DRAWN BY: RICK	CHECKED BY: RAJ
SCALE: AS SHOWN	

RICHARD A. JENKINS, P.E.
PE NO.: 68365
DATE: 13 OCT 11